



SRI GURU NANAK DEV KHALSA COLLEGE

(UNIVERSITY OF DELHI)

NAAC Accredited A

DEV NAGAR, NEW DELHI-110 005

Ref. No.: SGND/Admin/25/10187

Dated: 18/08/2025

CORRIGENDUM

Corrigendum for Revised Items of Work in the Quotation

In Continuation of the inviting notice for Repair and Painting Work vide Quotation inviting Notice Ref. No. SGND/Admin/25/10186, dt. 13/08/2025, the following correction is issued.

The Description of items of work (**Annexure-I**) has been revised as the items serial number were not in proper order and some items were duplicate. In view of the above, the items and their description have been corrected.


The remaining part of the quotation remains unchanged.

(Dr. Baljeet Singh)

Oftg. Principal.



subject :-Canteen Repair and painting work and other misc work at SGND Khalsa College, Karol Bagh, New Delhi					
Quotation					
Item No.	Sub-Head and Item of Work	Quantity	Unit	Rate	Amount
Item No. 1	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.				
	Total	1594.83	sqm		
Item No. 2	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.				
	Total	45.49	sqm		
Item No. 3	Providing and applying white cement based putty of average thickness 1 mm, of JK/ Birla- HIL/Asian make over the plastered wall surface to prepare the surface even and smooth complete.				
	Total	495.68	sqm		
Item No. 4	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq.meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-Charge. With cement mortar 1:4 (1 cement 4 fine sand)				
	Total	45.49	sqm		
Item No. 5	Painting with synthetic enamel paint of AsianApolite enamel / nerolac synthetic enamel / Dulex Enamel make to give an even shade : Two or more coats on new work				
	Total	261.78	sqm		
Item No. 6	Distempering with oil bound washable distemper of Asian- tractor UNO/ Nerolac- Beauty Acrylic Distemper/ Berger-Bison make to give an even shade :New work (two or more coats) over and including water thinnable priming coat with cement primer				
	Total	1594.83	sqm		


 Ofg. Principal
 SGND Khalsa College
 (University of Delhi)
 Dev Nagar, New Delhi-5



Item No. 7	Providing and laying Vitrified tiles				
	Total	15.01	sqm		

Item no 8	Providing and aplying waterproofing treatment				
	Total	82.23	sqm		
					-
			Sub total		-
			GST (as applicable)		
			Total amount in figures		

Amount in figures



Oftg. Principal
SGND Khalsa College
(University of Delhi)
Dev Nagar, New Delhi-5